



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 9163992

Procuring Entity METALS INDUSTRY RESEARCH & DEVELOPMENT CENTER

Title Supply of labor and materials for the Re-routing of drainage line of ATD Mechanical Lab's LPG Testing Facility

Area of Delivery Metro Manila

Solicitation Number:	22101476	Status	Closed
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	4
Classification:	Civil Works	Bid Supplements	0
Category:	Construction Projects		
Approved Budget for the Contract:	PHP 113,041.26	Document Request List	2
Delivery Period:	30 Day/s		
Client Agency:		Date Published	27/10/2022
Contact Person:	REYNALDO O BAYOT OIC FAD-SMU Gen. Santos Avenue Bicutan Taguig City Metro Manila Philippines 1631 63-2-8370431 robayot@mirdc.dost.gov.ph	Last Updated / Time	27/10/2022 00:00 AM
		Closing Date / Time	02/11/2022 16:00 PM
Description See attached scope of work, plan and blank BOQ Other Information For inquiries pls call our project Engrs Eric C. Calanno and Nestor Colibao at 8837-0431 to 38 Local 403 and 490 and Procurement Unit at local 443 and 444.			

Created by Minda B Bardiano

Date Created 26/10/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

Republic of the Philippines
METALS INDUSTRY RESEARCH AND DEVELOPMENT CENTER
Gen. Santos Ave., Bicutan, Taguig, Metro Manila
Tel. Nos. (02) 8837-0431 to 38 locals 443 & 444
Direct Line: (02) 8837-0430

SMU 003
Rev. 9/02-02-22

SUPPLIER:	DATE: Oct 26, 2022	PR NO: 22101476	PURPOSE: Supply of Labor and Materials for the Re-routing of drainage line of ATD Mechanical Lab's LPG Testing Facility
ADDRESS:	END-USER: FAD-GMU		

REQUEST FOR QUOTATION

(This is not an order)

To whom it may concern:

Please quote hereunder your lowest NET PRICES to the government on items listed below giving full and detailed description of your offers and stating the shortest time of delivery.

Kindly submit this quotation in a sealed envelope or email thru a password protected file, if Approved Budget of the Contract (ABC) is Php500,000.00 and below Php1,000,000.00, addressed to the Metals Industry Research & Development Center, plainly marking the aforesaid envelop with the following: "Proposal for furnishing MIRDC, with items of supplies/materials/ equipment/services (as the case may be) to be opened on _____ at _____ am/pm at the MIRDC, Gen. Santos Ave., Bicutan, Taguig, Metro Manila.

Canvassed by:

Rey Bayot

Very truly yours,

REYNALDO O. BAYOT

Head, Supply Management Unit

ITEM NO.	QUANTITY	UNIT	DESCRIPTION	UNIT PRICE
1	1	lot	Supply of Labor and Materials for the Re-routing of drainage line of ATD Mechanical Lab's LPG Testing Facility	

CONTACT PERSON:	VAT REGISTRATION NO.:		DISCOUNT:
TELEPHONE NO.:	VAT - <input type="checkbox"/>	VAT INCLUSIVE <input type="checkbox"/>	DELIVERY CHARGE:
	NON-VAT - <input type="checkbox"/>	VAT EXCLUSIVE <input type="checkbox"/>	
PAYMENT TERMS:	DELIVERY TERMS:	PRICE VALIDITY:	WARRANTY:

I certify that the aforementioned prices are true and correct.

_____	_____	_____
Firm or Dealer	Nationality	Signature

Supply of Labor and Materials for the Re-routing of the Drainage line of ATD Mechanical Lab's LPG Testing Facility

Scope of Work :


1. Contractor shall conduct an ocular/site inspection prior to the submission of a proposal.
2. Contractor shall conduct excavation works at the required depth prior to pipe laying.
3. Contractor to remove the existing PVC piping line prior to replacement.
4. The contractor shall ensure the bedding of sand and gravel before laying of pipe.
5. Use PVC pipe, 6" in diameter to be laid at a 30-meter length drain line with a one (1) degree declination from the drain pipe installation point to the existing manhole. (See layout)
6. The contractor shall implement the right method of standard pipe installation. All necessary materials needed must be provided to complete the project.
7. The contractor shall fill back the excavated soil and perform compaction.
8. Existing manhole must be cleaned/cleared of accumulated waste materials/debris.
9. Enclose one side of the wall of the existing manhole from where the tapping of the new drain line shall commence. (See layout)
10. Provide concrete cover (100mm thick) for the said existing manhole.
11. Construction of an additional manhole (1m x 0.7m) midway along the length of the proposed drain pipe to include excavation, masonry, rebar works, and the provision of a concrete manhole cover 100 mm thick.
12. Hauling and disposal of waste/unnecessary materials outside of MIRDC.


Others :

- a. Contractor shall submit workers' barangay health certificate before deployment and submit daily COVID health check to monitor their health status before entering the Gold Building.

- b. The contractor shall be liable for any damages incurred during the implementation of the project.
- c. Approved budget for the contract is One Hundred Thirteen Thousand Forty-One and 26/100 (Php 113,041.26) .
- d. Delivery period for the project is 30 calendar days.
- e. One (1) year warranty upon project completion.

Prepared by:


NESTOR Q. COLIBAO JR.
Engineer II, FAD-AGSS-GMU/TWG


ERIC C. CALANNO
Engineer III, FAD – AGSS-GMU/TWG

Noted by:


AUREA T. MOTAS
Chief, FAD

Approved by:


ROBERT O. DIZON
Executive Director